

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Houghton

(County)

Located in:

Corner Code #

1. Public Land Survey

T 51N R 38W K7
T 51N R 38W F11

2. Property Controlling
in Section

S T R
S T R

3. Miscellaneous
Property in Sec.

S T R
S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

F11 Nov 28 1995
K7 Jun 01 1994

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
(K7) Section corner common to Sections 13-14-23-24. Corner reestablished in 1962 by Billy D. Buckler, and remonumented at Buckler's position in 1972 by Arthur O. Enger. Buckler originally reestablished the position by proportionate measurement. Enger placed a 1" I.D. x 14" iron pipe capped with a 4" dia. aluminum cap at the corner, which falls in Pike Lake Road. The 1963 and 1972 witnesses: 9" Elm N02E 59 links, 12" Sugar maple S02E 62 links, USC&GS BM N62W 95 links, 18" Sugar maple S50W 54.7'.
(F11) Quarter corner common to Sections 28-33. Corner reestablished in 1962 by Billy D. Buckler with the aid of testimony from a former local resident. Buckler placed a 1" I.D. iron pipe capped with a 4" aluminum cap at the corner position and marked the following NBTs: 13" Aspen N85E 42 links, 50" W. Pine stump N48E 80.5 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K7) Found the 1972 monument as described, in good condition, at the gravel surface of Pike Lake Road. The monument was found at substantial record bearing and distance from the Elm NBT, now a rotting stump with remains of the measuring notch visible; and from the 16" Sugar maple, found in good condition. The 12" Sugar has been destroyed by turnout construction, and the USC&GS monument was found destroyed. I drove the monument to approx. 12" below the road surface and made three new witnesses as described below.
(F11) Found the 1963 monument, a 1" I.D. iron pipe capped with a 4" dia. aluminum Michigan Dept. of Conservation tablet, in good condition, and at record bearing and distance from the 1963 witnesses. The Aspen is now dead. The W. Pine stump still stands, and has been burnt. Left the monument in place and marked 4 new accessories as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K7) Found 1" pipe with 4" MNHR cap and drove it to 12" below road surface.

Blazed and scribed the following:

5" Sugar N43W 77.4' "S14 NBT"
7" Sugar N33E 47.7' "S13 NBT"
8" Sugar S52E 57.7' "S24 NBT"

The 1972 NBT: 18" Sugar S54W 54.3'
Bearings are magnetic.

(F11) Found 1" pipe with 4" aluminum cap. Blazed and scribed the following new bearing trees:

9" Spruce N89E 28.1' (at base of old Aspen NBT) "1/4S NBT"

8" Maple S65E 16.5' "1/4S NBT"

10" Sugar N01W 45.2' "1/4S NBT"

6" Sugar S56W 53.0' "1/4S NBT"

Bearings are magnetic.



Signed by

Stephan J. Szyszkoski

Surveyor's Michigan License No.

33986

Date

3/13/97

For the Michigan Department of Natural Resources - Forest Management Division