

93

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Noughton

Located In:

Corner Code #

(County)

1. Public Land Survey

T 51N R 36W

112

T R

T R

T R

2. Property Controlling
In Section

S T R

S T R

3. Miscellaneous
Property In Sec.

S T R

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Aug 13 1997

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
(112) Quarter corner common to Sections 34-35. Corner reestablished in 1981 by Keith L. Sackett, RLS: "Restored on line midway between corners north and south. Set 1" I.D.x32" iron pipe with 4" aluminum cap. 4" Sugar N51E B.5', 6" Sugar N51W S.8', 7" Sugar S01W 15.7'".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(112) 1981 monument was not recovered. The monument was probably removed during nearby building construction. Found a large spike, probably set by a local surveyor, at approximate record bearing and at record distance from the two remaining 1981 NBTs: The Sugar NE and the Sugar NW. At the record position, and at the location of the spike, I placed a 1" I.D.x32" iron pipe capped with a yellow plastic cap stamped "MICH D.N.R. L.S. 33986". Marked two new witnesses as described below. The corner lies about 50' west of Fedie Road. Corner placed and witnessed by D.Lampela, Baraga District Office, MDNR. I note that the bearings to the 1981 witnesses are at variance with those measured this date. This is probably due to the large quantity of scrap metal immediately adjacent to the corner. Note that the angle between the 1981 witnesses is close to record. No measurements to other corners were made at this time. This corner is being rerecorded in order to update the monument and accessories.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(112) Set 1" pipe with plastic cap.

The 1981 witnesses:

4" Sugar N62E 8.5'

6" Sugar N38W 5.8'

Blazed and scribed the following:

12" Sugar N30E 48.6' "1/4S NBT"

5" Sugar N20E 19.2' "1/4S NBT"

The above bearings are magnetic.



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 9/2/97

For the Michigan Department of Natural Resources - Forest Management Division