

94

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Houghton _____
(County)

Located In: _____ Corner Code # _____

1. Public Land Survey T51N R 36W J12
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Aug 13 1997

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		●		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
(J12) Center of Section 35. Corner established in 1981 by Keith L. Sackett, RLS: "Set 1" I.D.x32" iron pipe with 4" aluminum cap. 7" Sugar N23W 8.2', 14" sugar S38E 14.2', 9" Sugar N88W 29.1'".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J12) Found the 1981 monument as described, in good condition, and at record bearing and distance from the two remaining 1981 accessories: the two Sugars in the NW. The stump remains of the Sugar SE (blazes visible) was also found at record bearing and distance. Left the monument in place and marked two new witnesses as described below. Corner recovered and re-witnessed by D.Lamola, Baraga District Office, MDNR. No measurements to other corners were made at this time. This corner is being rerecorded in order to update the accessories.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
(J12) Found 1" pipe with 4" MDNR cap.

The 1981 witnesses:
7" Sugar N18W 8.2'
9" Sugar N83W 29.1'
Blazed and scribed the following:
21" Y. Birch S12E 8.3' "1/4S BT"
8" Y. Birch N52E 45.7' "1/4S BT"
Placed a squared post adjacent.
Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 9/2/97
Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Forest Management Division