

90.

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Noughton

County	Located In:	Corner Code #
1. Public Land Survey	T 51N R 38W	J9
	T 51N R 38W	K9
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S 23 T 51N R 38W	15
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

K9 March 15, 1994  
15 March 21, 1994

I, Stephan J. Szyszkoski, in a field survey on J9 March 21, 1994, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE:** Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	19	20	21							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

(J9) Quarter corner common to Sections 23-28. Corner established in 1848 by S.W. Higgins and perpetuated as follows: Set 1/4 Section post on true line, Sugar 12 North 14, Spruce 10 S40W 23. Original line notes show stream crossings 11.87 ch. west and 2.69 ch. east of the corner, on the random. Found no subsequent record.

(K9) Section corner common to Sections 23-24-25-26. Corner restored in 1963 by Billy D. Buckler ALS, at a found old, scribed, cedar post. Corner was re-monumented with a 1" pipe and 4" aluminum Mich. Dept. of Conservation cap and the following NBTs: 13' Hard Maple (S25 NBT) S56E 67 links, 12" Y. Birch (S28 NBT) S30W 59 links, 15" Soft Maple (S23 NBT) N28W 77 links.

(15-Sec. 23) West 1/10 corner between Sections 23-26. Corner not established in the original survey. Found no subsequent record.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(J9) Original post and accessories not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner midway and on a straight line between monumented section corners 2686.84' east and west. From the reestablished position, the stream call east checks to a moderately well defined stream described as in the record. To the west, the stream meanders much, and does not check with the record, being 13.38 chains west of the corner. At the position for the corner, I placed a 1" I.D. x 36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.

(K9) Found and accepted Buckler's monument as described, at record bearing and distance from the 1963 bearing trees: the Y. Birch being a dead stub. The maple NBTs are in good condition. Marked two new bearing trees as described below.

(15-Sec. 23) Found no evidence of prior monumentation at the corner position. Established the corner midway and on a straight line between monumented Quarter and Section corners 1343.42' east and west. At the position for the corner, I placed a 1" I.D. x 36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(J9) Set a 1" pipe with 4" MDNR cap. Blazed and scribed the following new bearing trees:

9" Sugar N44W 12.7' 1/4S NBT  
8" Sugar N44E 9.1' 1/4S NBT  
7" Sugar S48E 9.1' 1/4S NBT  
6" Sugar S62W 18.4' 1/4S NBT

Bearings are magnetic. Distances are horizontal distances. Placed a 4" squared sugar post adjacent to the corner.

(K9) Found 1" pipe with 4" MDNR cap. Blazed and scribed the following new bearing trees:

7" Sugar N52E 3.0' S24 NBT  
10" Cherry S45W 21.7' S26 NBT  
Bearings are magnetic.

(15) Set 1" pipe with 4" MDNR cap.

Blazed and scribed the following bearing trees:

10" Yellow Birch N88W 22.5' 1/16S BT  
8" Sugar N45W 18.5' 1/16S BT  
10" Yellow Birch S45E 5.0' 1/16S BT  
5" Sugar N78E 26.0' 1/16S BT  
Bearings are magnetic. Placed a 4" squared sugar post adjacent.

Signed by Stephan J. Szyszkoski Date 3-21-94  
Surveyor's Michigan License No. 33986

