

89

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
HOUGHTON
 (County)

	Located in:	Corner Code #?
1. Public Land Survey	T <u>51N</u> R <u>36W</u>	<u>87</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>30</u> T <u>51N</u> R <u>36W</u>	<u>3 3</u>
	S <u>30</u> T <u>51N</u> R <u>36W</u>	<u>10</u>
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Stephan J. Szyszkoski, in a field survey on July 07, 1992, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	1	2	3	4	5	6	7	8	9	10	11	12	13
3	14	15	16	17	18	19	20	21	22	23	24	25	26
4	27	28	29	30	31	32	33	34	35	36	37	38	39
5	40	41	42	43	44	45	46	47	48	49	50	51	52
6	53	54	55	56	57	58	59	60	61	62	63	64	65
7	66	67	68	69	70	71	72	73	74	75	76	77	78
8	79	80	81	82	83	84	85	86	87	88	89	90	91
9	92	93	94	95	96	97	98	99	100	101	102	103	104
10	105	106	107	108	109	110	111	112	113	114	115	116	117
11	118	119	120	121	122	123	124	125	126	127	128	129	130
12	131	132	133	134	135	136	137	138	139	140	141	142	143
13	144	145	146	147	148	149	150	151	152	153	154	155	156

A. Description of original monument and accessories and/or subsequent restoration:

- (87) Quarter corner between Sections 19 and 30, T51N-R36W. Corner established by U.S. Deputy Surveyor S.W. Higgins, 1948. Original bearing trees: Maple 8 N51E 8, Sugar 8 N70W 18. Found no subsequent record.
- (3) North 1/16 corner between Section 30, T51N-R36W and Section 25, T51N-R37W. Corner not established in original survey. Found no subsequent record.
- (10) South 1/16 corner between Section 30, T51N-R36W and Section 25, T51N-R37W. Corner not established in original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (89) Original post and accessories not recovered. Found no monumentation or evidence of use at corner location. Determined corner to be lost and reestablished corner by single proportionate measure to the original record between adjacent recorded corners 2594.75' West and 2640.96' East.
- (7) Established corner midway and on a straight line between recorded corners A9 and A10. Found no monumentation or evidence of use at this position.
- (10) Established corner midway and on a straight line between recorded corners A10 and A11. Found a 1.5" diameter iron pipe 4.1' West of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | |
|---|--|--|
| <ul style="list-style-type: none"> (89) Placed a 1"x36" iron pipe capped with a 4" dia. cast aluminum MDMR tablet. Blazed and scribed the following new bearing trees:
 12" Sugar S54E 6.3' (1/4S NBT)
 8" Sugar S13W 14.1' (1/4S NBT)
 7" Sugar N22W 10.0' (1/4S NBT)
 11" Sugar N26E 13.1' (1/4S NBT)
 Squared a 3" Hemlock North 1.3' | <ul style="list-style-type: none"> (3) Placed a 1"x36" iron pipe capped with a 4" dia. cast aluminum MDMR tablet. Blazed and scribed the following bearing trees:
 7" Sugar N38E 11.8' (1/16S BT)
 9" Sugar S97E 30.4' (1/16S BT)
 6" Sugar S17E 4.8' (1/16S BT)
 12" Y. Birch S81W 7.4' measured on slope (1/16S BT). Placed a 4" squared maple post South 1'. | <ul style="list-style-type: none"> (10) Placed a 1"x36" iron pipe capped with a 4" dia. cast aluminum MDMR tablet. Blazed and scribed the following bearing trees:
 11" Y. Birch N23E 4.8' (1/16S BT)
 16" Y. Birch S70E 14.2' (1/16S BT)
 23" Hemlock S52W 22.2' (1/16S BT)
 24" Hemlock N29W 11.2' (1/16S BT)
 Squared and scribed a 4" Hemlock S32E 2.1' |
|---|--|--|

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 7-14-92

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1979
 REVISED BY _____ JAN. 14, 1975
 JANUARY, 1983

