

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
HOUGHTON

County	Located in:	Corner Code \neq
1. Public Land Survey	T 51N R 36W	C10
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 19 T 51N R 36W	14
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Stephen J. Szyszkoski, in a field survey on C10 June 11, 1992, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	1	2	3	4	5	6	7	8	9	10	11	12	13
3													
4	7	8	9	10	11	12							
5													
6	13	14	15	16	17	18							
7													
8	19	20	21	22	23	24							
9													
10	25	26	27	28	29	30							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(C10) Quarter corner between Sections 29 and 30, T51N-R36W. Corner established by U.S. Deputy Surveyor S.W. Higgins, 1848. Original bearing trees: Hemlock 10 N35W 38, Birch 12 S85E 25.

(14) South 1/16 corner between Sections 19 and 20, T51N-R36W. Corner not established in original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C10) Restored corner position at record bearing and distance from the original Birch bearing tree. Any evidence of the Hemlock bearing tree has been destroyed by road construction. The Birch is a live 20" Y. Birch with both upper and lower blazes, all scribing, and measuring notch visible. Signatures on the upper blaze date at least to 1951. A 16" Cedar signature tree bears S73E, 28.7' from the restored corner. Earliest date found on this tree is 1947.

(14) Established corner midway and on a straight line between recorded corners C8 and C9. From the monumented corner, a found 1-1/4" alumina pipe bears N49W 91.0'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C10) Drove a 1"x36" iron pipe capped with a 4" dia. cast alumina MDNR tablet to 6" below gravel surface of N-S road. Blazed and scribed the following new bearing trees:

8" Cedar S53E 30.3' (1/4S NBT)
 8" Maple N64E 26.9' (1/4S NBT)
 10" Cedar N31W 59.5' (1/4S NBT)
 7" Cedar S30W 63.8' (1/4S NBT)
 Center of N-S road is West 3'.



(14) Placed a 1"x36" iron pipe capped with a 4" dia. cast alumina MDNR tablet. Blazed and scribed the following bearing trees:
 12" Cedar S75W 18.5' (1/16S BT)
 20" Cedar N40W 31.2' (1/16S BT)
 9" Cedar N32E 19.7' (1/16S BT)
 8" Maple S25E 17.1' (1/16S BT)
 Placed a 5" cedar post South 1.2'

Signed by Stephen J. Szyszkoski Date 7-14-92
 Surveyor's Michigan License No. 33986