

**SURVEY & REMONUMENTATION**

**JAN 09 1998**

APPROVED LAND CORNER  
P.A. 345 OF 1990  
Houghton County

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**SECTION**

Houghton Located In: Corner Code #  
(County)  
1. Public Land Survey T 52N R 34W M-2\*  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

NANCY FENILI 12/11/97  
HOUGHTON COUNTY 11:25  
LC 3/ 461 PAU Fee: 11.00  
Page 1 of 2

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Michael Mileski, in a field survey on 8 July, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970; the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-2; East One-quarter Corner Section 1, T52N, R34W;  
See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-2; East One-quarter Corner Section 1, T52N, R34W;  
Found a 1 1/8" x 36" steel rod pointed at one end projecting 10" above ground as recovered by Keith Sackett, PS in 1977. Replaced this monument with a 1" (I.D.) x 36" galvanized iron pipe with cap stamped as to location. Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-2; East One-quarter Corner Section 1, T52N, R34W;  
Set a 1" (I.D.) x 36" galvanized iron pipe with cap stamped as to location projecting 6" above ground.

- i) Set 7" spike SE/side 8" Yellow Birch N82°E 64.75'
- ii) Set 7" spike SW/side 17" Sugar Maple S51°E 13.47'
- iii) Set 7" spike E/side 7" Sugar Maple S24°W 49.60'
- iv) Set 7" spike N/side 11" Sugar Maple S78°W 5.70'
- v) Set 7" spike S/side 10" Sugar Maple N50°W 27.79'
- vi) Set 7" spike S/side 20" Sugar Maple N15°W 3.16'
- 6' Steel fence post w/ yellow sign North 1.5'

(i), (iii), (iv), and (v) are marked with upper and lower blazes. The lower blaze is scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.

(ii) and (vi) are Mr. Sackett's new bearing trees and are further described in Part A. These new bearing trees were also painted red.

\* This corner is also A-2 of T52N, R33W.



Signed by [Signature] Date 11 Dec 1997  
Surveyor's Michigan License No. 39091

LC  
3-461

A. Description of original monument and accessories and/or subsequent restoration:

M-2; East One-quarter Corner Section 1, T52N, R34W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1845 and monumented with a wood post witnessed by a

Sugar 6 S23°E 26 lks.

and a

Lynn 14 N36°W 20 lks.

On 20 April 1977, Keith Sackett, P.S. #19006 recovered and accepted a "1 (in.) steel axle shaft". According to a Land Corner Recordation Certificate prepared by Mr. Sackett dated 3 August 1977 and recorded on 20 December 1977 in Volume 1 on page 489 of the Houghton County Land Corner Records, this monument was left in place and the following accessories were established:

20" Sugar N15°W 2.4'  
Presently alive and 20" in diameter but leaning heavily to the east and showing signs of decay. Both blazes are partially healed and scribing is visible.  
Set 7" spike S/side Measured N15°W 3.16'

16" Sugar S50°E 12.6'  
Presently alive and 17" in diameter having a healed upper blaze and a partially healed lower blaze with scribing visible.  
Set 7" spike SW/side Measured S51°E 13.47'

9" Sugar N58E° 22.5'  
Found dead and fallen.

04777