

JAN 09 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Robert W. Campbell
For corners in
DEC. 10, 1997
Houghton
(County)

SECTION

NANCY FENILI 12/11/97
HOUGHTON COUNTY 11:24
LC 3/ 459 PAU Fee: 11.00
Page 1 of 2

1. Public Land Survey	T 52N R 34W	M-3*
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael Mileski, in a field survey on 10 November, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A. Description of original monument and accessories and/or subsequent restoration:

M-3; Section Corner common to Sections 1 and 12, T52N, R34W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1845 and monumented with a wood post witnessed by a Sugar 14 N57°W 12 lks. and a Sugar 8 N46°E 34lks.

During the subdivision of T52N, R33W, by William Burt, D.S. in 1849, this corner was not rewitnessed.

A cruiser's report prepared by Peter Larsen dated August/September 1905 indicates this corner as being monumented by an "iron post set by Sherman". No accessories are noted. A corner sketch prepared by Edward Charles, P.S. #12580, possibly in 1972, indicates the following accessories:

Tree	N25°10'E	35.90'
Fence corner	N27°45'E	25.90'
Iron pipe on fence line	S49°22'W	29.33'
Fence corner	N49°23'W	20.90'

Mr. Charles' sketch does not indicate the type of monument.

On 12 April 1973 Arthur Enger, P.S. #13581 recovered and accepted a 1" x 24" iron pin. According to a Land Corner Recordation Certificate prepared by Mr. Enger dated 28 December 1973 and recorded on 1 August 1974 in Liber 1 on page 123 of the Baraga County Land Corner Records, this monument was replaced with a 1" (I.D.) x 36" iron pipe with 4" aluminum cap witnessed by a PK Nail in fence corner post N46°W (mag.) 20.90' and a PK Nail in Box Elder 12 N25°E (mag.) 35.90'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-3; Section Corner common to Sections 1 and 12, T52N, R34W;

Found a 1" (I.D.) x 36" iron pipe with 4" aluminum cap 12 inches below the surface. This monument is located at the east edge of a farm field approximately 15 feet west of an old fence running north. I left Mr. Enger's monument in place and stamped "PA 345 1997" to the cap. Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-3; Section Corner common to Sections 1 and 12, T52N, R34W;

See back of form. *This corner is also A-3 of T52N, R33W.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													



Signed by [Signature]
Surveyor's Michigan License No. 39091

Date 11 Dec 1997

3-459
L 4

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-3; Section Corner common to Sections 1 and 12, T52N, R34W;

Found a 1" (I.D.) iron pipe with 4" aluminum cap 12 inches below the ground.

Set 7" spike	W/side	8" Box Elder	N09°E	73.21'
Set 7" spike	W/side	13" Box Elder	N28°E	29.00'
Set 7" spike	N/side	6" Box Elder	S71°E	61.05'
		6" Steel fence post w/ yellow sign	East	10.0'

All of the above new bearing trees are marked with upper and lower blazes.
The lower blaze is scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.

6660
04777

SEARCHED
SERIALIZED
INDEXED
FILED