

APPROVED LAND CORNER
P.A. 345 OF 1990
Houghton County

Robert W. Coulter
DEC. 10, 1997

For corners in

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY & REMONUMENTATION

JAN 09 1998

SECTION

Houghton
(County)
Located In: _____ Corner Code # _____
1. Public Land Survey T 52N R 34W M-4*
T _____ R _____
T _____ R _____
T _____ R _____
2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

NANCY FENILI 12/11/97
HOUGHTON COUNTY 11:25
LC 3/ 463 PAU Fee: 11.00
Page 1 of 2

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael Mileski, in a field survey on 11 November, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-4; East One-quarter Corner Section 12, T52N, R34W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-4; East One-quarter Corner Section 12, T52N, R34W;

Found a 1" diameter galvanized iron pipe with 4" aluminum cap as set by Keith Sackett, P.S. #19006 of the Michigan Department of Natural Resources. This monument was most likely set during the mid-1970's and bears approximately N10°30'W 3.3 feet from the single proportioned position. This corner falls in an abandoned north-south powerline corridor. Accepted Mr. Sackett's monument as a careful and faithful reestablishment of the position of the original corner. I did not remonument the corner, but stamped "PA 345 1997" to the cap.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-4; East One-quarter Corner Section 12, T52N, R34W;

Found a 1" diameter galvanized iron pipe with 4" aluminum cap stamped as to location projecting 12" above ground.

- | | | | | | |
|-------|--------------|---------|---|-------|--------|
| i) | Set 7" spike | N/side | 5" Hemlock | N79°E | 55.02' |
| ii) | Set 7" spike | W/side | 12" Yellow Birch | S32°E | 65.31' |
| iii) | Set 7" spike | SE/side | 7" Hemlock | S40°W | 37.13' |
| iv) | Set 7" spike | N/side | 9" Sugar Maple | S84°W | 39.10' |
| v) | Set 7" spike | E/side | 17" Red Maple | N12°W | 66.54' |
| vi) | Set 7" spike | S/side | 15" Sugar Maple | S53°W | 24.58' |
| vii) | Set 7" spike | N/side | 24" Twin Red Maple | N69°W | 34.04' |
| viii) | | | 6' Steel fence post w/ yellow sign East | | 1.5' |

(i), (ii), (iii), (iv), and (v) are marked with upper and lower blazes. The lower blaze is scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.

(vi) and (vii) are presumably Mr. Sackett's new bearing trees having partially healed upper and lower blazes with scribing visible. Both blazes and a band around the tree at the upper blaze were painted red.

*This corner is also A-4 of T52N, R33W.

Signed by *Michael Mileski*

Date 11 Dec 1997

Surveyor's Michigan License No. 39091

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													



3-1163
LC
77

A. Description of original monument and accessories and/or subsequent restoration:

M-4; East One-quarter Corner Section 12, T52N, R34W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1845 and monumented with a wood post witnessed by a

Fir 12 N34°E 33 lks.

and a

Hemlock 14 N35°W 7 lks.

This corner was recovered and perpetuated by Peter A. Larsen in 1905. According to his cruiser's report dated August/September 1905, Mr. Larsen states that the fir U.S. bearing tree is "rotted" and that the hemlock U.S. bearing tree has "fallen down" and that he set a "cedar 1/4 post" witnessed by a

Sugar 9 N37°W 13 lks.

and a

Birch 17 N08°E 27 lks.

64777

01300 188

UNITED STATES DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT