

SURVEY & REMONUMENTATION

JAN 09 1998

APPROVED LAND CORNER

P.A. 345 OF 1990

Houghton County

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Robert W. Mileski

Fortcorners in Dec. 10, 1997

SECTION 12711/97

Houghton (County)

Located In:

Corner Code #

NANCY FENILI

HOUGHTON COUNTY

LC

3/ 465 PAU Fee:

11:26

11.00

Page 1 of 2

1. Public Land Survey

T 52N R 34W

M-5*

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

I, Michael Mileski, in a field survey on 20 November, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-5; Section Corner common to Sections 12 and 13, T52N, R34W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-5; Section Corner common to Sections 12 and 13, T52N, R34W;

Found a 1/2" x 18" iron rod set over a 1" x 24" galvanized iron pipe with a broken 4" aluminum cap at the intersection of the centerlines of Askel Road and Tower Road. Replaced found monuments with a 1" (I.D.) x 36" galvanized iron pipe with cap set inside of a monument box. Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-5; Section Corner common to Sections 12 and 13, T52N, R34W;

Set a 1" (I.D.) x 36" galvanized iron pipe with cap inside a cast iron monument box.

Set 7" spike	NW/side	6' Cedar Fence Corner	N61°E	38.42'
Set 7" spike	SW/side	8" Aspen	S36°E	55.71'
Set 7" spike	NW/side	5" Red Maple	S30°W	139.82'
Set 7" spike	NW/side	6" White Birch	S47°W	108.29'
Set 7" spike	SE/side	Power Pole	S59°W	63.67'
Set 7" spike	NW/side	6" Red Maple	N29°W	156.18'

All of the above new bearing trees are marked with upper and lower blazes. The lower blaze is scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.

*This corner is also A-5 of T52N, R33W.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													



Signed by [Signature] Surveyor's Michigan License No. 39091

Date 11 Dec 1997

LC
S-405

A. Description of original monument and accessories and/or subsequent restoration:

M-5; Section Corner common to Sections 12 and 13, T52N, R34W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1845 and monumented with a wood post witnessed by a

Yellow Birch 14 N39°W 25 lks.

and a

Hemlock 30 N69°E 17 lks.

During the subdivision of T52N, R33W, by William Burt, D.S. in 1849, this corner was further witnessed by a

Hemlock 30 N65°E 17 lks.

and a

Sugar 7 S53°E 62 lks.

This corner was reestablished on 13 April 1973 by Arthur Enger, P.S. #13581 "at intersection of approximate construction centerlines of a N & S county road and a county road going W, which are presumed to be the section lines by common report". According to a Land Corner Recordation Certificate prepared by Mr. Enger dated 28 December 1973 and recorded in Liber 1 on page 123 of the Baraga County Land Corner Records, this corner was monumented with a 1" (I.D.) x 24" iron pipe with 4" aluminum cap witnessed by a

Nail in Power Pole S62°W (mag.) 66.19'

Stop Sign Post S16°E (mag.) 44.3'

Telephone Jct. Box N36°W (mag.) 94.0'

11/10

APR 13 1973
ARTHUR ENGER
P.S. #13581