

JAN 09 1998

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

APPRO. SURVEYOR

P.A. 345

Houghton County

For Robert W. Myleski  
DEC. 10, 1997

Houghton

(County)

Located In:

Corner Code #

NANCY FENILI 12/11/97

HOUGHTON COUNTY

11:26

LC 3/ 467 PAU Fee: 9.00

Page 1 of 1

- 1. Public Land Survey T 52N R 34W M-6\*
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Michael Mileski, in a field survey on 10 November, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-6; East One-quarter Corner Section 13, T52N, R34W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1845 and monumented with a wood post witnessed by a

Hemlock 6 N16°E 20 lks. and a Sugar 12 N69°W 40 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-6; East One-quarter Corner Section 13, T52N, R34W;

This corner was reestablished midway and on line between controlling government corners immediately to the north and south. The corner location falls 2.5 feet west of the physical centerline of a north-south, 20-foot wide, graded gravel road. This corner position is on the extension of the remains of an east-west fence line to the west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-6; East One-quarter Corner Section 13, T52N, R34W;

Set a 1" (I.D.) x 36" galvanized iron pipe with cap stamped as to location 12" below the road surface.

- i) Set 7" spike E/side 6" Aspen N40°E 62.83'
- ii) Set 7" spike N/side 4" Sugar Maple N62°E 101.28'
- iii) Set 7" spike SW/side 5" Aspen S35°E 58.44'
- iv) Set 7" spike NE/side Power Pole N39°W 59.71'
- 6' Steel fence post w/ yellow sign East 33.0'

(i), (ii), and (iii) are marked with upper and lower blazes. The lower blaze is marked "NBT". Both blazes and a band around the tree at the upper blaze were painted red.

(iv) is marked with a vertical red stripe at shoulder height.

\*This corner is also A-6 of T52N, R33W.



Signed by \_\_\_\_\_  
Surveyor's Michigan License No. 39091

Date 11 Dec 1997