

APPROVED LAND CORNER
P.A. 345 01
Houghton County

SURVEY & REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

JAN 09 1998

Robert W. Gault
DEC. 10, 1997

SECTION 12/11/97
HOUGHTON COUNTY 11:27
LC 3/ 470 PAU Fee: 9.00
Page 1 of 1

<u>Houghton</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>52N</u> R <u>34W</u>	<u>M-8*</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael Mileski, in a field survey on 10 November, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-8; East One-quarter Corner Section 24, T52N, R34W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1845 and monumented with a wood post witnessed by a Black Oak 8 N60°E 21 lks. and a Cedar 5 N30°W 16 lks.

No subsequent record evidence bearing upon the location of this corner was found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-8; East One-quarter Corner Section 24, T52N, R34W;

This corner was considered lost and reestablished midway and on line between controlling government corners immediately to the north and south. This corner position falls 3.5 feet east of the physical centerline of a north-south, 10-foot wide, woods road which runs along the entire east line of section 24.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-8; East One-quarter Corner Section 24, T52N, R34W;

Set a 1" (I.D.) x 36" galvanized iron pipe and cap stamped as to location 12" below the road surface.

Set 7" spike	NW/side	8" Sugar Maple	N34°E	32.64'
Set 7" spike	N/side	13" Sugar Maple	S66°E	34.88'
Set 7" spike	NW/side	8" Sugar Maple	S50°W	52.83'
Set 7" spike	S/side	10" Sugar Maple	N69°W	80.42'
		6' Steel fence post w/ yellow sign	East	20.0'

All of the above new bearing trees are marked with upper and lower blazes. The lower blaze is scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.

*This corner is also A-8 of T52N, R33W.

Signed by *Michael Mileski*

Date 11 Dec 1997

Surveyor's Michigan License No. 39091

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

