

JAN 09 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

APPROVED LAND CORNER
No. 10
Robert W. Conner
For corners in Dec. 10, 1997

SECTION

NANCY FENILI 12/11/97
HOUGHTON COUNTY 11:27
LC 3/ 471 PAU Fee: 11.00
Page 1 of 2

<u>Houghton</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>52N</u> R <u>34W</u>	<u>M-9*</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael Mileski, in a field survey on 16 July, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3		2	1
3													
4	7			8			9			10		11	12
5													
6	18			17			16			15		14	13
7													
8	19			20			21			22		23	24
9													
10	30			29			28			27		26	25
11													
12	31			32			33			34		35	36
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-9; Section Corner common to Sections 24 and 25, T52N, R34W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-9; Section Corner common to Sections 24 and 25, T52N, R34W;

Set a 1" (I.D.) x 36" galvanized iron pipe from Mr. Sackett's bearing trees. This corner is located at the intersection of trail roads to the north, south, and west. Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-9; Section Corner common to Sections 24 and 25, T52N, R34W;

Set a 1" (I.D.) x 36" galvanized iron pipe with cap stamped as to location.

Set 7" spike	SE/side	7" Sugar Maple	N71°E	69.67'
Set 7" spike	W/side	8" Sugar Maple	S21°E	82.00'
Set 7" spike	NW/side	14" Sugar Maple	S63°W	54.81'
Set 7" spike	NE/side	8" Sugar Maple	N36°W	70.73'
		6" Steel fence post w/ yellow sign	East	20'

All of the above new bearing trees are marked with upper and lower blazes. The lower blaze is scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.

*This corner is also A-9 of T52N, R33W.



Signed by [Signature]
Surveyor's Michigan License No. 39091

Date 11 Dec 1997

A. Description of original monument and accessories and/or subsequent restoration:

M-9; Section Corner Common to Sections 24 and 25, T52N, R34W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1845 and monumented with a wood post witnessed by a

Sugar 7 S25°W 31 lks.

and a

Yellow Birch 14 N77°E 47 lks.

During the subdivision of T52N, R33W, by William Burt, D.S. in 1849, this corner was further witnessed by a

Sugar 30 S52°E 32 lks.

and a

Yellow Birch 12 N77°E 46 lks.

On 22 April 1977, Keith Sackett, P.S. #19006 recovered and accepted a "1¼ (in.) I.D. x unknown length iron pipe one foot above ground in line with roads north, south and west. Old blazed line east." According to a Land Corner Recordation Certificate prepared by Mr. Sackett dated 3 August 1977 and recorded on 20 December 1977 in Volume 1 on page 483 of the Houghton County Land Corner Records, this monument was left in place and the following accessories were established:

10" Sugar S30°W 32.3'

Presently alive and 12" in diameter having healed upper and lower blazes.

Set 7" spike NW/side Measured S28°W 32.81'

9" Sugar S82°E 24.2'

Presently alive and 12" in diameter having healed upper and lower blazes.

Set 7" spike N/side S82°E 24.77'

7" Sugar N42°W 45.0'

This bearing tree was logged. The stump was found intact but possibly displaced by machinery.

Measured N42°W 44.4'

3-471
C

7777

1977
1977