

JAN 09 1998

APPROVED LAND CORNER
P.A. 370
Houghton County

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For recordation
Robert W. Camp
DEC 10, 1997
Houghton
(County)

Located In: _____ Corner Code # NANCY FENILI 12/11/97
HOUGHTON COUNTY #
LC. 3/ 473 PAU Fee: 11:27
Page 1 of 1 9.00

- 1. Public Land Survey T 52N R 34W
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling in Section S _____ T _____ R _____
S _____ T _____ R _____
- 3. Miscellaneous Property in Sec. S _____ T _____ R _____
S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Michael Mileski, in a field survey on 12 November, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-10; East One-quarter Corner Section 25, T52N, R34W;
Originally established during U.S. Survey conducted by William Burt, D.S. in 1845 and monumented with a wood post witnessed by a
Cedar 6 N47°E 21 lks.
and a
Cedar 12 N78°W 15 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-10; East One-quarter Corner Section 25, T52N, R34W;
No evidence of corner location was found. This corner was considered lost and reestablished midway and on line between controlling government corners immediately to the north and south. This corner is located in a transitional zone of high grass, black ash, red maple, and tag alder.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-10; East One-quarter Corner Section 25, T52N, R34W;
Set a 1" (I.D.) x 72" galvanized iron pipe and cap stamped as to location projecting 12" above ground.
Set 7" spike NW/side 10" Red Maple N13°E 52.58'
Set 7" spike N/side 10" Red Maple N84°E 45.08'
Set 7" spike W/side 12" Red Maple S17°E 21.59'
(in cluster of 5)
Set 7" spike E/side 9" Black Ash South 61.10'
Set 7" spike SW/side 6" Black Ash N42°W 54.01'
Set 7" spike NE/side 9" Red Maple N35°W 22.36'
6' Steel fence post w/ yellow sign East 1.5'



All of the above new bearing trees are marked with upper and lower blazes. The lower blaze is scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.

*This corner is also A-10 of T52N; R33W.

Signed by Michael Mileski
Surveyor's Michigan License No. 39091

Date 11 Dec 1997