

JAN 09 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

APPLICANT'S LAND CORNER

P.A. 74

Houghton

Robert W. Mileski

For corners in DEC 10, 1997

Houghton

(County)

Located In:

Corner Code #

NANCY FENILI 12/11/97

HOUGHTON COUNTY

11:28

LC 3/ 474 PAU Fee: 11.00

Page 1 of 2

1. Public Land Survey

T 52N R 34W

M-11*

T R

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous

S T R

Property in Sec.

S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Michael Mileski, in a field survey on 23 July, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-11; Section Corner common to Sections 25 and 36, T52N, R34W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-11; Section Corner common to Sections 25 and 36, T52N, R34W;

Found a 1" x 15" drill steel flush with the ground. Fences run to the north and west. Replaced found monument with a 1" (I.D.) x 36" galvanized iron pipe with cap. Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-11; Section Corner common to Sections 25 and 36, T52N, R34W;

Set a 1" (I.D.) x 36" galvanized iron pipe with cap appropriately stamped as to location projecting 3" above ground.

Set 7" spike	NW/side	7" Elm	N35°E	22.93'
Set 7" spike	N/side	7" Elm	N84°E	9.65'
Set 7" spike	SW/side	12" Red Maple	S19°E	57.41'
Set 7" spike	SW/side	6" Elm	N37°W	3.13'
		6' Steel fence post w/ yellow sign	North	5.0'

All of the above new bearing trees are marked with upper and lower blazes. The lower blaze is scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.

*This corner is also A-11 of T52N, R33W.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													



Signed by *Michael Mileski*
Surveyor's Michigan License No. 39091

Date 11 Dec 1997

Feb-8
27

A. Description of original monument and accessories and/or subsequent restoration:

M-11; Section Corner common to Sections 25 and 36, T52N, R34W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1845 and monumented with a wood post witnessed by a

Sugar 14 N43°E 37 lks.

and a

Sugar 6 N10°W 34 lks.

During the subdivision of T52N, R33W, by William Burt, D.S. in 1849, this corner was further witnessed by a

Sugar 6 S28°E 17 lks.

and a

Sugar 12 N41°E 36 lks.

On 20 November 1984, Robert Crampton, P.S. #24391 recovered and accepted a "1 (in.) hex. steel pin at the intersection of two old fences and on a projection of a road to the east". According to a Land Corner Recordation Certificate prepared by Mr. Crampton dated 20 December 1984 and recorded on 20 December 1984 in Volume 2 on page 119 of the Houghton County Land Corner Records, this monument was left in place and witnessed by a

3" Box Elder N15°E 35.77'
Presently alive and 4" in diameter.
Measured N16°E 36.05'

4" Box Elder S67°E 48.0'
Presently alive and 6" in diameter.
Measured S66°E 47.89'

14" Twin Yellow Birch S41°W 17.75'
Presently alive and 14" in diameter.
I added an upper and lower blaze. The lower blaze was scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.
Set 7" spike NW/side Measured S43°W 18.23'

16" Yellow Birch S82°W 28.50'
Presently alive and 16" in diameter.
I added an upper and lower blaze. The lower blaze was scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.
Set 7" spike N/side Measured S83°W 29.60'

1" Thin Wall Steel Tubing N87°E 60.75'
Found 1" steel pipe 2" above ground.
Measured N88°E 60.70'

64777