

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>52</u> N. S., R. <u>34</u> W.	M-7, M-9
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER _____

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner M-7: Original monument and accessories not found. Found 1½" I.D. x unknown length iron pipe buried in old logging road. Fits good with corners north and south.

Corner M-9: Original monument and accessories not found. Found 1¼" I.D. x unknown length iron pipe one foot above ground in line with roads north, south and west. Old blazed line east.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner M-7: Re-established 4-18-77 at pipe.

Corner M-9: Re-established 4-22-77 at pipe.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner M-7: 1½" I.D. x unknown length iron pipe buried in old logging road.

9" Sugar S58°W 18.4' S24, NBT
 12" Sugar N69°W 19.2' S13, NBT
 16" Maple N80°E 16.2', S18, NBT

Corner M-9: 1¼" I.D. x unknown length iron pipe one foot above ground.

10" Sugar S30°W 32.3' S25, NBT
 9" Sugar S82°E 24.2' S30, NBT
 7" Sugar N42°W 45.0' S24, NBT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE August 3, 1977
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Keith L. Sackett
 Michigan Dept. of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

