

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>52</u> N. <u>34</u> R. <u>34</u> X W.	<u>M2, M1</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner M2: Original monument and accessories not found. Found 1" steel axle shaft and numerous blazes.

Corner M1: Original monument and accessories not found. Found numerous blazes in area.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner M2: Re-established 7-20-77 at axle shaft. Fits good with river south and corners north. Numerous blazes in area.

Corner M1: Re-established 7-18-77 by double proportion. Good north-south blazed line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner M2: 1" I.D. x unknown length steel axle shaft.
 20" Sugar N15°W 2.4' ¼S NBT
 16" Sugar S50°E 12.6' ¼S NBT
 9" Sugar N58°E 22.5' ¼S NBT

Corner M1: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.
 6" Sugar N83°E 13.8' S31NBT
 7" Maple S49°W 8.5' S 1 NBT
 8" Sugar N69°W 12.0' S36 NBT
 Sq. 6" Sugar N35°E 3.4'

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE August 3, 1977
 CHIEF OF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR
 Keith L. Sackett
 Michigan Dept. of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

