

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Houghton</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S <u>24</u> T <u>52N</u> R <u>35W</u>	<u>12</u>
	S <u>24</u> T <u>52N</u> R <u>35W</u>	<u>16</u>
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Sep 20 2000

I, Stephan J. Szyszkoski, in a field survey on _____, 19___ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(12-Sec. 24) South 1/16 corner, Section 24. Not established in the original survey.
 (16-Sec. 24) East 1/16 corner between Sections 24-25. Established in 1972 by A.O.Enger, RLS. 1" ID x 36" iron pipe with 4" aluminum cap. Elm 14 South 8.1', Elm 12 S80W 4.4'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(12-Sec. 24) Established midway and on a straight line between center of section (unmonumented) 1323.06' north and quarter corner 1323.06' south.
 (16-Sec. 24) Found the 1972 monument, a 1" ID iron pipe with the 1972 aluminum cap broken off by a fallen tree. Otherwise, it is in good condition. Found the monument at record bearing and distance from the now-dead 1972 elm NBTs, both with scribing visible. Accepted the monument as a careful and faithful establishment of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(12) Set 1" IDx32" IP with 4" aluminum MDNR cap. Blazed and scribed: 14" W.Spruce N32E 47.3' "1/16S 8T" 12" W.Spruce S57E 13.7' do 8" Maple S53.5W 24.3' do 6" Maple(w'ly of two) N34W 31.2' do Bearings are magnetic. Distances to notch in lower blaze.	(16) Found 1" IP with broken aluminum cap. Blazed and scribed the following: 8" Balsam N32E 21.3' "1/16S 8T" 14" Cedar S15E 55.7' do 22" W.Spruce S8W 44.8' do 25" W.Spruce S58W 22.9' do Bearings are magnetic. Distances are to notch in lower blaze.
---	--



Signed by Stephan J. Szyszkoski Date 10/31/00
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Forest Management Division