

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Houghton
 (County)

Located In: Corner Code #

- | | | | |
|------------------------------------|------|-------------|-------|
| 1. Public Land Survey | T | R | _____ |
| | T | R | _____ |
| | T | R | _____ |
| | T | R | _____ |
| 2. Property Controlling in Section | S 15 | T 52N R 35W | 5 |
| | S 15 | T 52N R 35W | 4 |
| 3. Miscellaneous Property in Sec. | S | T | R |
| | S | T | R |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

4 Aug 26 1999
 5 Aug 25 1999

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |


- A. Description of original monument and accessories and/or subsequent restoration:
 (5-Sec. 15) North 1/16 corner, Section 15. Corner monumented in 1980 by K.L.Sackett, RLS. "Set 1" I.D. x 36" iron pipe. 16" Sugar East 4.8', 12" Sugar N60W 21.8', 12" Sugar S70W 12.5'.
 (4-Sec. 15) Northwest 1/16 corner, Section 15. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(5-Sec. 15) Recovered the 1980 monument, at record bearing and distance from the 1980 accessories and determined that it was placed at an erroneous position about 46' south of the position intended in 1980. I removed the 1980 monument and defaced the 1980 witnesses. I established the corner midway and on a straight line between Quarter corner 1295.91' north and Center of Section 1295.91' south. At the position for the corner, I placed a 1" ID x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.
 (4-Sec. 15) Found no evidence of prior monumentation at the corner position. Established the corner at the intersection of straight lines connecting opposite 1/16 corners. At the position for the corner, I placed a 1" x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|--|
| (5) Set 1" pipe with 4" MDNR cap. Blazed and scribed the following: 12" Sugar N33E 31.1' "1/16S BT" 5" Y. Birch S22E 7.2' do 8" Y. Birch N85W 3.9' do 5" Sugar N46W 20.2' do | (4) Set 1" pipe with 4" MDNR cap. Blazed and scribed the following: 8" Sugar N28W 13.95' "1/16S BT" 7" Sugar N86E 15.0' do 7" Y. Birch S25W 31.7' do 6" Maple N74W 5.65' do |
|---|--|
- Bearings are magnetic. Distances are to notch in lower blaze.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 10/19/99

For the Michigan Department of Natural Resources - Forest Management Division