

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Houghton</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 52H R 35W	I6
	T 52H R 35W	F7
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Jul 06 1999

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:  
 (I6) Quarter corner common to Sections 14-15. Corner monumented in 1953 by Dean C. DeLaMater: 1" pipe with 4" brass cap. 10" Y. Birch N78E 16 links, 12" S. Maple S04E 46 links. Found no subsequent record.  
 (F7) Quarter corner common to Sections 16-21. Corner monumented in 1953 by Dean C. DeLaMater: 1" pipe with 4" brass cap. 6" H. Maple S46W 18 links, 9" H. Maple N78E 13 links. Found no subsequent record.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I6) Recovered the 1953 monument, a 1" ID iron pipe capped with a 4" brass MI Dept. of Conservation tablet, as described, in good condition, and at record bearing and distance from the 1953 witnesses, both recovered in good condition with old overgrown blazes. The Y. Birch is 16" N85E, and the R. Maple is 14" S03E (magnetic brgs.). Left the monument in place and marked two new witnesses as described below.  
 (F7) Recovered the 1953 monument as described, a 1" ID iron pipe capped with a 4" brass MI Dept. of Conservation tablet, in good condition, and at record bearing and distance from the 1953 witnesses: 9" Sugar S54W 11.4' with overgrown blazes, and 12" Sugar N85E 8.5' with overgrown blazes. Left the monument in place and marked two new witnesses as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I6) Found 1" pipe with 4" brass cap.  
 Blazed and scribed two new witnesses:  
 8" Hemlock S82W 8.1' "1/4S N8T"  
 6" Sugar N07E 10.2' do  
 Bearings are magnetic. Distances to notch in lower blaze. Placed a squared cedar post adjacent.

(F7) Found 1" pipe with 4" brass cap.  
 Blazed and scribed the following:  
 5" Sugar S06W 10.9' "1/4S N8T"  
 16" Y. Birch N28E 29.6' do  
 Bearings are magnetic. Distances are to notch in lower blaze. Placed a squared 6" sugar post adjacent.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 12/19/99

For the Michigan Department of Natural Resources - Forest Management Division