

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Houghton</u>	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>52N</u> R <u>35W</u>	<u>J11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>35</u> T <u>52N</u> R <u>35W</u>	<u>2</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Nov 07 2001

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11										●	●		
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
 (J11) Quarter corner common to Sections 26-35. 1978: Reestablished at P.A.Larson iron pipe by Keith L. Sackett, RLS. 1"IDx36" iron pipe with 4" brass cap. 7" Sugar N37E 3.4', 5" Sugar N72W 14.6', 7" Yellow Birch S02W 13.8'.
 (2-Sec. 35) East 1/16 corner between Sections 26-35. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J11) Recovered the 1978 monument, a 1"ID iron pipe with brass MI Dept. of Conservation tablet, in good condition, and at record bearing and distance from the 1978 accessories. The two Sugars are in good condition. The Y.Birch is a rotting stump with scribing visible. Left the monument in place and made new witnesses as described below.
 (2-Sec. 35) Established the corner midway and on a line of mean true bearing between Quarter corner 1319.13' west and Section corner 1319.13' east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J11) Fd. 1" ID iron pipe with 4" brass cap. Blazed and scribed:	(2) Set 1"IDx32" iron pipe with 4" alum. MDNR cap. Blazed and scribed:
9" Y.Birch S53E 29.4' "1/4S N8T"	10" Sugar S52W 16.8' "1/16S 8T"
7" Sugar S06W 32.7' do	10" Sugar N68W 25.5' do
The 1978 wits:	8" Y.Birch N01E 20.5' do
10" Sugar N36E 3.4' overgrown blazes	9" Sugar S59E 18.6' do
8" Sugar N70W 14.6' do	Set squared cedar post adjacent.
Set cedar post adjacent. Bearings are magnetic. Distances to notch in lower blaze.	Bearings are magnetic. Distances to notch in lower blaze.



Signed by Stephan J. Szyszkoski Date 11/8/01
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Office of Property Management