

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Houghton  
(County)

Located In: Corner Code #

- |                                    |                         |       |
|------------------------------------|-------------------------|-------|
| 1. Public Land Survey              | T 52N R 35W             | J13   |
|                                    | T 52N R 35W             | J12   |
|                                    | T _____ R _____         | _____ |
|                                    | T _____ R _____         | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
|                                    | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____ | _____ |
|                                    | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Dec 12 2001

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34								
13												

**A. Description of original monument and accessories and/or subsequent restoration:**  
(J13) Corner common to Section 35 T52N-R35W and Section 2 T51N-R35W. Reestablished by single proportionate measurement in 1962 by Billy D. Buckler. 1" iron pipe with 4" aluminum cap. 9" Soft Maple S66W 33 links, 17" W.Spruce N30W 52 links.  
(J12) Center of Section 35. Established in 1978 by K.L.Sackett. 1"IDx40" iron pipe with 4" aluminum cap. 8" Maple S46E 5.6', 7" Sugar N32E 8.0', 9" Y.Birch S69W 8.5'.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**  
(J13) Recovered the 1962 monument as described, in good condition but for a fractured cap, and at record bearing and distance from the 1962 accessories found as follows: 11" Maple S70W 22.2' overgrown blazes, W.Spruce stump, rotting, N30W 34.3'. Left the monument in place and made three new 8Ts as described below.  
(J12) Recovered the 1978 monument as described, in good condition, and at record bearing and distance from the remaining accessories recovered as follows: 8" Sugar N35E 7.9' overgrown blazes, 11" Y.Birch S72W 8.6' "1/4S 8T". The Maple SE is gone. Left the monument in place and made two new witnesses as described below.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**  
(J13) Found 1"ID iron pipe with 4" aluminum MI Dept. of Conservation cap. Blazed and scribed:  
6" Maple N30E 11.7' "1/4S N8T"  
15" W.Spruce S69E 37.3' do  
6" Sugar S24W 19.2' do  
Squared spruce post adjacent. Bearings are magnetic. Distances to notch in lower blaze.  
(J12) Found 1"ID iron pipe with 4" alum. MDNR cap. Blazed and scribed:  
8" Y.Birch S64E 21.1' "C1/4 8T"  
14" Y.Birch N53W 34.7' do  
Squared a 10" Ash S60W 1.6' to center of tree. Bearings are magnetic. Distances are to notch in lower blaze.



Signed by Stephan J. Szyszkoski Date 2/27/02  
Surveyor's Michigan License No. 33986