

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Houghton  
 (County)

Located In: Corner Code #

1. Public Land Survey	T	R	_____
	T	R	_____
	T	R	_____
	T	R	_____
2. Property Controlling in Section	S 35	T 52N R 35W	11
	S 35	T 52N R 35W	4
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

4 Dec 20 2001  
 11 Dec 19 2001

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and/or subsequent restoration:**  
 (11-Sec. 35) Southwest 1/16 corner, Sec. 35. Not established in the original survey.  
 (4-Sec. 35) Northwest 1/16 corner, Sec. 35. Corner not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(11-Sec. 35) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.  
 (4-Sec. 35) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(11) Set 1"IDx32" I.Pipe with 4" alum. MDNR cap. Blazed and scribed:	(4) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed and scribed:
12" Hemlock S31E 80.7' "1/16S BT"	9" Hemlock N56E 67.1' "1/16S BT"
5" Sugar S21E 30.0' do	4" Y.Birch S49E 38.6' do
3" Poplar West 16.2' do	16" Hemlock S11W 57.7' do
4" Poplar N12W 33.4' do	6" Hemlock N68W 79.5' do
Squared cedar post adjacent. Bearings are magnetic. Distances are to notch in lower blaze.	Squared cedar post adjacent. Bearings are magnetic. Distances are to notch in lower blaze.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 2/27/02