

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Houghton

 (County)

Located In: _____ Corner Code # _____

1. Public Land Survey
 T _____ R _____
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling
 in Section S 25 T 52N R 35W SW-NE 1/64
 S 25 T 52N R 35W 5

3. Miscellaneous
 Property in Sec. S _____ T _____ R _____
 S _____ T _____ R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Sep 27 2004

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
 (SW-NE 1/64 corner, Sec. 25) Center of the SW1/4 of the NE1/4 of Section 25. Not established in the original survey.
 (5-Sec. 25) North 1/16 corner, Section 25. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (SW-NE 1/64) Established the corner at the intersection of straight lines connecting opposite 1/64 corners.
 (5-Sec. 25) Established the corner midway and on a straight line between Quarter corner 1316.31' north and Center of Section 1316.31' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(SW-NE 1/64) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 5" Cedar N13E 20.5' mrkd "1/64S 8T" 14" Spruce N42E 23.1' do 7" Spruce S34W 4.0' do 6" Maple in clump N59W 31.9' do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with plastic tag.	(5) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 7" Maple N29E 18.7' mrkd "1/16S 8T" 6" Maple S44E 21.7' do 5" Maple S67W 25.4' do 7" Spruce N17W 8.5' do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with plastic tag.
--	--



Signed by Stephan J. Szyszkoski Date 11/16/04
 Surveyor's Michigan License No. 33986