

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Houghton

(County)

Located In:	Corner Code #
1. Public Land Survey	T ___ R ___
	T ___ R ___
	T ___ R ___
	T ___ R ___
2. Property Controlling in Section	S 25 T 52N R 35W W-E 1/64
	S 25 T 52N R 35W NW-SE 1/64
3. Miscellaneous Property in Sec.	S ___ T ___ R ___
	S ___ T ___ R ___

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Sep 28 2004

I, Stephan J. Szyszkoski, in a field survey on _____, 19___ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

(W-E 1/64 corner, Sec. 25) The Southeast corner of the SW1/4 of the SW1/4 of the NE1/4 of Section 25. Not established in the original survey.

(NW-SE 1/64 corner, Sec. 25) The southeast corner of the NW1/4 of the NW1/4 of the SE1/4 of Section 25. Not established in the original survey

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(W-E 1/64) Established the corner midway and on a straight line between Center of Section 666.04' West and and 1/16 corner #9 666.04' East. Note: the monument installed at this position is about 4' south of the water's edge of Bear Creek on a beach sand shelf, about 3' below the surface of the adjoining high ground.

(NW-SE 1/64) Established the corner at the intersection of straight lines connecting opposite 1/64 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(W-E 1/64) Set 1"X32" I.pipe with 4" alum. MDNR cap. Set measuring nails in:
 12" Cedar N09E 50.2' mrkd "1/64S BT"
 10" Elm S31E 31.5' do
 9" Elm S10W 40.6' do
 12" Spruce N55W 20.8' do
 Set sq'd cedar post on high ground adjacent. Bearings are magnetic. Distances are to nail with plastic tag.

(NW-SE 1/64) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in:
 5" Cedar N72E 45.6' mrkd "1/64 S BT"
 10" Maple S55E 21.0' do
 5" Maple S58W 13.6' do
 4" Sugar N59W 25.7' do
 Bearings are magnetic. Distances are to nail with plastic tag. Sq'd an 18" Poplar N10W 0.8' to SE face.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 11/16/04

For the Michigan Department of Natural Resources - Office of Land and Facilities