

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Houghton  
 (County)

Located In:	Corner Code #
1. Public Land Survey	T52N R 35W M10
	T R
	T R
	T R
2. Property Controlling in Section	S25 T52N R 35W 6
	S T R
3. Miscellaneous Property in Sec.	S T R
	S T R

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Sep 29 2004

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

(M10) Quarter corner common to Section 25 T52N-R35W and Section 30 T52N-R34W. 1972 - re-monumented by A.O.Enger RLS at the location of a found 1" iron pin and rotted off scribed post. Set 1"IDx36" iron pipe with 4" aluminum cap. Red Maple 4 N30W 29.4', Red Maple 6 N29E 35.4'.  
 (6-Sec. 25) Northeast 1/16 corner, Section 25. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(M10) Found the 1972 monument, a 1"ID iron pipe, aluminum cap missing, bent over, having been apparently struck by a road grader. The lower portion of the monument was found firmly set and plumb and this position was accepted as the position for the corner. The R.Maple NBT NW was not recovered. The R.Maple NBT NE is now a clump of approx. 1" dia. Maples. Installed a new monument at the corner position.  
 (6-Sec.25) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(M10) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 7" Balsam N34E 7.5' mrkd "1/4S NBT" 7" twin Maple N77W 67.1' do 6" Maple N49W 17.8' do 6" dbl Sugar N03W 22.4' do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with plastic tag.	(6) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 10" Spruce S89E 42.5' mrkd "1/16S BT" 7" Maple S15E 9.1' do 6" Cedar S67W 49.2' do 5" Spruce N58W 12.2' do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with plastic tag.
---	--



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 11/16/04

For the Michigan Department of Natural Resources - Office of Land and Facilities