

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Houghton</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>52N</u> R <u>35W</u>	<u>B1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	S _____ T _____ R _____	_____
2. Property Controlling in Section	S <u>6</u> T <u>52N</u> R <u>35W</u>	<u>5</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1	6											
2		5		4		3		2		1		
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

Jun 11 2007

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

(B1) North 1/4 corner, Section 6. Not established in the original survey. The original GLO plat for T52N-R35W gives the position for the corner 41.41 chains east of the Township corner and 40 chains west of the closing section corner between Sections 5 and 6.  
 (5-Sec. 6) North 1/16 corner, Section 6. Not established in the original survey. From the original GLO plat for T52N-R35W, I calculate that the parenthetical distance from this corner to the N1/4 corner of Section 6 is 19.649 chains, and to the Center of Section 6, 20.00 chains.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(B1) Established the corner on the Township line between T52N-R35W and T53N-R35W, being the line between the Township corner 2738.23' west and the Standard Section corner between Sections 31 and 32, T53N-R35W (the original 1/4 corner on the South side of Sec. 31 having not been recovered), and at 40 chains, proportionate to the original record, west of closing Section corner B1, 2645.00' east. The monumented Standard Quarter Corner on the south line of Sec. 31 T53N-R35W is 5.25' east. The corner falls 16' south of the center of an E-W gravel drive.  
 (5-Sec. 6) Established the corner on the N-S 1/4 line of Section 6, 20 chains, proportionate to the original record, north of the Center of Section 6 (1341.77' M) and 19.649 chains south of the Quarter corner on the north side of Sec. 6 (1318.22' M).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(B1) Set 1"IDx32" I.pipe with 4" alum. MDNR cap, flush with ground. Set measuring nails in: 7" Sugar S87W 24.8' no marks made 6" Poplar N06W 40.6' do 6" Poplar N27E 40.6' do The NW corner of a mobile home bears S13E 20.9' Bearings are magnetic. Distance to trees are to nail w/MDNR tag.	(5) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 6" Sugar N04W 28.7' wrkd "1/16 BT" 12" Sugar S70E 13.3' do 10" Sugar S28E 17.8' do 17" Sugar N68W 28.8' do Set sq'd sugar post adjacent. Bearings are magnetic. Distances are to nail with MDNR tag.
--	---



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 7/12/07