

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Houghton</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>52N</u> R <u>35W</u>	<u>C1</u>
	T <u>52N</u> R <u>35W</u>	<u>B2</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims

B2 Jun 11 2007  
 C1 Jun 12 2007

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

(C1) Closing Section corner between Sections 5 and 6. 1846 - Established by S.W.Higgins, Deputy Surveyor, 8 links west of Standard corner on the Township line. Set post. Ironwood 9 South 15 links, Sugar 16 S55W 41 links. 1940 - W.A.Waara, for Copper Range Company, erroneously notes this corner to be common with the Standard Section corner. He found a 1 1/4" I.P. 1.5' above ground and noted the following: 14" Y.Birch marked by cruisers N1E 19.4', 7" S.Map. marked by cruisers N69E 27', Put Y.tag on 7" R.Map.(crotched) N44W 28.5', Marked 4" S.Map. S28E 16.4'.  
 (B2) Center of Section 6. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C1) The original post and accessories were not recovered. Found a 1 1/4" I.pipe projecting 1.7' above ground. Bearing and distance to a 14" Sugar S29E 17.3' check closely with Waara's 4" S.Map. but markings not visible. Found a 1" I.P., also projecting 1.7' a.g. 5.17' east, origin unknown, corresponding to the Standard corner. Accepted the 1 1/4" pipe as the best available evidence of the position of the original corner. This pipe is 0.13' S. of the Township line defined by the Standard corners.  
 (B2) Established the corner at the intersection of straight lines connecting opposite 1/4 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C1) Found 1.25" ID I.pipe. Set measuring nails in: 14" Sugar S29E 17.3' mrkd "S5 NBT" 5" Sugar N76W 7.4' "S31 NBT" 6" Sugar N28W 12.45' "S31 NBT" 7" Sugar N81E 7.7' "S32 NBT" Distances are to nail with MDNR tag. Fd. 1" ID I.P. East 5.17' Bearings are magnetic. Set sq'd Sugar post adjacent.	(B2) Set 1" IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 14" Sugar N43E 21.5' mrkd "C1/4 BT" 7" Sugar S30E 16.2' do 5" Sugar S45W 20.6' do 15" Sugar N38W 46.2' do Set sq'd Sugar post adjacent. Bearings are magnetic. Distances are to nail with MDNR tag.
--	--



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 7/12/07

For the Michigan Department of Natural Resources, Office of Land and Facilities