

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Houghton</u> <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T 52N R 35W	E8	
	T 52N R 35W	H9	
2. Property Controlling in Section	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims			

Register of Deeds Stamp & File Number

I, Stephan J. Szyszkoski, in a field survey on E8 11/09/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E8) Quarter corner common to Sections 20-21. 1846 - Established by S.W.Higgins Deputy Surveyor. Set post. Sugar 14" N45W 30 links, Sugar 10" S53E 22 links. Notes of P.A. and M.C.Larsen: 1925 - B.T. Sugar S.E. Stdg - set post from same. 1963 - Billy D. Buckler RLS remonumented the corner at the position of a wood post set by M.C.Larsen, Hancock. Corner lies 40.40 chains South of Original Section corner and checks with stream and hill to North, 1/2 mile to South is short. Set 1"ID iron pipe with 4" aluminum cap. 11" Hard Maple N76W 41 links, 13" Hard Maple N54E 44 links.

(H9) Quarter corner common to Sections 22-27. 1846 - Established by S.W.Higgins, Deputy Surveyor. Set post. Sugar 8" N60E 20 links, Y.Birch 24" S62W 27 links. Notes of P.A. and M.C.Larsen state: "1963 - Found blaze and notch at base of rotted sugar and set cedar post in old blazed line - should be close". 1963 - Billy D. Buckler RLS remonumented the corner at the position of M.C.Larsen post. Set 1"Iron pipe with 4" aluminum cap. 6" Y.Birch N23W 23 links, 8" Y.Birch S57E 30 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E8) Found the 1963 monument in good condition and at record bearing and distance from the Sugar NBT NW, in good condition with overgrown blazes. The Sugar NBT NE was not found. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

(H9) Found the 1963 Buckler monument bent and with cap broken. The two Y.Birch NBTs are at record bearing and distance, and in good condition with overgrown blazes. Recovered the lower portion of the pipe monument plumb and placed a new monument at that position and in accord with the 1963 NBTs. Accepted the 1963 position as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E8) Found 1"ID I.pipe with 4" alum. MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:
 15" Sugar N72W 27.4' old blazes 1963 NBT
 4" Sugar N34E 19.5' mrkd "1/4S NBT"
 17" Maple S45E 19.6' do
 15" Maple N32W 14.0' do
 Sq'd cedar post adjacent.
 Bearings are magnetic.

(H9) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 11" Y.Birch S49E 19.8' old blazes 1963 NBT
 9" Y.Birch N20W 15.4' do do
 12" Sugar S83E 29.1' mrkd "1/4S NBT"
 5" Hemlock S52W 30.05' do
 Set sq'd Cedar post adjacent.
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 11/17/2009



For the Michigan Department of Natural Resources, Office of Land and Facilities