

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Houghton COUNTY
T 52N R 35W

DESCRIPTION OF CORNER 1/4 corner between Sections 12 and 13

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED May 24, 1972

WITNESSES TO CORNER..... Red Maple 11 N12°E (mag.) 13.9 ft. "1/4S, NBT"



Red Maple 10 S40°E (mag.) 24.1 ft. "1/4S, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner re-established proportionately on line between section corners 40.174 ch. W and 40.184 ch. E. Corner falls 8 lks. S of a down E & W fence wire and S79°W 41 lks. from an old down fence corner, but could find no evidence to show the fence corner was located at the 1/4 corner.

SURVEYOR'S SEAL

DISTRIBUTION:

Forestry Division, Lansing

Area Forester

District Surveyor

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE

September 1, 1972