


STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD

Houghton COUNTY  
T 52N R 34-35W

DESCRIPTION OF CORNER Section Corner 19, 24, 25, and 30  
CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap  
DATE MONUMENT PLACED AND WITNESSED June 8, 1972  
WITNESSES TO CORNER..... W. Spruce 8 S57°E (mag.) 13.5 ft. "S30, NBT"



W. Spruce 9 N½°W (mag.) 30.5 ft. "S24, NBT"  
W. Spruce 5 S50°W (mag.) 54.6 ft. "S25, NBT"  
AND  
W. Spruce 10 N78°E (mag.) 26.3 ft. "S19, NBT"

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found an old scribed wood post at an old fence corner. Checked the post and fence corner for alinement and distance from corners 1/2 mile S and 2 miles N, as well as with natural features noted in original field notes, and found them to be consistent with the record; therefore, I accepted them as being at or near the original corner location.

SURVEYOR'S SEAL

DISTRIBUTION:

Forestry Division, Lansing

Area Forester

District Surveyor

SIGNED

*Arthur O. Enger*  
REGISTERED LAND SURVEYOR  
Arthur O. Enger

DATE

July 25, 1972