

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Houghton COUNTY


T 52N R 35W

DESCRIPTION OF CORNER 1/4 corner between Sections 13 and 24

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED June 7, 1972

WITNESSES TO CORNER..... Red Maple 5 N63°W (mag.) 16.7 ft. "1/4S, NBT"



Red Maple 5 S7°E (mag.) 36.5 ft. "1/4S, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner re-established on line between section corners 39.649 ch. to E and to W. Found a fence corner N27°W 64 lks., but it does not match up with an E & W fence one-quarter mile E, which does follow the section line as found here.

SURVEYOR'S SEAL

DISTRIBUTION:

Forestry Division, Lansing

Area Forester

District Surveyor

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE

July 21, 1972