

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD


Houghton COUNTY  
T 52N R 35W

DESCRIPTION OF CORNER Section Corner 23, 24, 25, and 26

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED June 6, 1972

WITNESSES TO CORNER..... Sugar Maple 10 N 7°W (mag.) 8.5 ft. "S23, NBT"



Sugar Maple 12 S69°W (mag.) 10.0 ft. "S26, NBT"

Sugar Maple 12 S16°E (mag.) 7.8 ft. "S25, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Being at a loss as to how to reconcile the calls of the original field notes with conditions actually encountered on the ground, I finally concluded that the most consistency was obtained by extending the section line from Sec. Cor. 22, 23, 26, and 27 (existing original) E'ly through the 1/4 cor. bet. Sec. 23 and 26 (existing original), and beyond, a distance equal to that between the aforementioned corners, and establishing the corner at that point. Found this point to check most favorably with stream crossings in the area. The original subdivision of this township was very erratic, and almost any corner position is plausible.

SURVEYOR'S SEAL

DISTRIBUTION:

Forestry Division, Lansing

Area Forester

District Surveyor

SIGNED

*Arthur O. Enger*  
REGISTERED LAND SURVEYOR  
Arthur O. Enger

DATE

July 21, 1972