

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Houghton COUNTY
T 52N R 35W

DESCRIPTION OF CORNER 1/4 corner between Sections 13 and 14

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED June 5, 1972

WITNESSES TO CORNER..... W. Spruce 3 S39°E (mag.) 13.4 ft. "1/4S, NBT"



Sugar Maple 5 S25°W (mag.) 21.1 ft. "1/4S, NBT"

W. Pine 7 N41°E (mag.) 53.0 ft. "1/4S, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

No subsequent monuments found, except for a forester's approximate post
843°W 1.23 chains.

Corner re-established on line between section corners 39.082 ch. to N and
to S.

SURVEYOR'S SEAL

DISTRIBUTION:

Forestry Division, Lansing

Area Forester

District Surveyor

SIGNED

Arthur O. Eger
REGISTERED LAND SURVEYOR
Arthur O. Eger

DATE

October 30, 1972