

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Houghton COUNTY
T 52N R 34-35W

DESCRIPTION OF CORNER 1/4 corner between Sections 13 and 18

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED June 1, 1972

WITNESSES TO CORNER..... NW corner of old garage S57 $\frac{1}{2}$ ^oE (mag.) 44.9 ft.



Nail in power pole S59^oW (mag.) 38.2 ft.

Fence corner East 33 ft.

AND (Monument buried about 6 inches below road surface)

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner assumed to fall in a road intersection. Re-established corner at intersection of road centerlines as determined by parallel fences on N & S sides of E & W road and E & W sides of N & S road. This position is in line with an old fence going E from the intersection, also.

SURVEYOR'S SEAL

DISTRIBUTION:

Forestry Division, Lansing

Area Forester

District Surveyor

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE

October 30, 1972