

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Cloughton

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____ S. _____ R. _____ E. _____ W. _____		
2. PROPERTY CONTROLLING IN SECTION <u>14</u> T. <u>52</u> S. R. <u>35</u> E. <u>EX</u> W.		14 & 16
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ S. _____ R. _____ E. _____ W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on see below 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Neither corner established in original survey nor subsequently apparently, except that Corner 14 had been marked approximately by a forester's post S52°W 2.075 ch. from the corner.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner 14: Established 6/5/72 on line between section corner 19.541 ch. S and 1/4 corner 19.541 ch. N.

Corner 16: Established 6/7/72 on line between section corner 19.905 ch. E and 1/4 corner 19.905 ch. W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monuments for both corners: 1" I.D. x 36" iron pipe with 4" aluminum cap.

Witnesses for Corner 14: Sugar Maple 9 S34°W (mag.) 27.0 ft. "1/16S, BT"
Elm 8 N6°E (mag.) 29.1 ft. "1/16S, BT"

Witnesses for Corner 16: Red Maple 6 S76°E (mag.) 7.2 ft. "1/16S, BT"
Red Maple 5 N86°W (mag.) 21.3 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE February 28, 1973

MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581