

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. _____ N. _____ E. _____ S. R. _____ W.	_____
2. PROPERTY CONTROLLING IN SECTION <u>13</u>	T. <u>52N</u> N. _____ E. <u>35</u> XX S. R. _____ W.	1, 3, & 16
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. _____ S. R. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on see below 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

None of these corners established in original survey nor subsequently, apparently, except Corner 16, which falls as nearly as can be determined by ocular estimation, at the intersection of the W'ly projection of an E & W fence line to the east and an old field edge to the south.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner 1: Established 6/13/72 on line between section corner 20.087 ch. W and 1/4 corner 20.087 ch. E. Found an 8" aspen with grown-over blazes on four sides N31°E 12 lks., for an approx. corner.
- Corner 3: Established 6/5/72 on line between section corner 19.541 ch. N and 1/4 corner 19.541 ch. S.
- Corner 16: Established 6/7/72 on line between 1/4 corner 19.820 ch. W and section corner 19.820 ch. E, which falls at the position noted in A above.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monuments for all three corners: 1" I.D. x 36" iron pipe with 4" aluminum cap.

- Witnesses for Corner 1: Cedar 9 N79°W (mag.) 35.8 ft. "1/16S, BT"
Cedar 9 N31°E (mag.) 37.8 ft. "1/16S, BT"
- Witnesses for Corner 3: Red Maple 5 S26°W (mag.) 6.0 ft. "1/16S, BT"
Red Maple 4 N30½°E (mag.) 5.2 ft. "1/16S, BT"
- Witnesses for Corner 16: Red Maple 8 N 8°W (mag.) 33.5 ft. "1/16S, BT"
Red Maple 4 S57°W (mag.) 33.5 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE March 2, 1973
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

Arthur O. Enger
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581