

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
2. PROPERTY CONTROLLING IN SECTION <u>25</u>	T. <u>52</u> N. _____ S. _____ R. <u>35</u> <sup>XP.</sup> E. _____ W. _____	<u>#1, 2, 3, &amp; 7</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
 FILING NUMBER \_\_\_\_\_

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on see below 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

None of these corners established in original survey nor subsequently, apparently, except Corner 7, which falls at an fence corner.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- Corner 1: Established 6/6/72 on line between section corner 20.050 ch. W and 1/4 corner 20.050 ch. E.
- Corner 2: Established 6/8/72 on line between 1/4 corner 20.050 ch. W and section corner 20.050 ch. E.
- Corner 3: Established 6/6/72 on line between 1/4 corner 19.920 ch. W and section corner 19.920 ch. E.
- Corner 7: Established 6/8/72 at an old fence corner, which was found to be on line between section corner 19.976 ch. N and 1/4 corner 19.976 ch. S.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Monuments for all four corners: 1" I.D. x 36" iron pipe with 4" aluminum cap.

- Witnesses for Corner 1: W. Spruce 6 N78°W (mag.) 11.4 ft. "1/16S, BT"  
W. Spruce 4 N50°E (mag.) 30.9 ft. "1/16S, BT"
- Witnesses for Corner 2: Elm 14 South (mag.) 8.1 ft. "1/16S, BT"  
Elm 12 S80°W (mag.) 4.4 ft. "1/16S, BT"
- Witnesses for Corner 3: Red Maple 8 N27°W (mag.) 29.1 ft. "1/16S, BT"  
(Distances horizontal) Sugar Maple 8 S22°W (mag.) 14.9 ft. "1/16S, BT"
- Witnesses for Corner 7: Sugar Maple 9 S52°E (mag.) 30.9 ft. "1/16S, BT"  
Red Maple 6 S16°W (mag.) 4.4 ft. "1/16S, BT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE March 2, 1973  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

**Michigan Department of Natural Resources**

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581