

✓

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 52. NR. 35 W.

Houghton

COUNTY

DESCRIPTION OF CORNER Section corner common to Sec.'s 5-6-7-8
DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap
WITNESSES TO CORNER 8" W. Pine S 65° W 13 links
"S 7 NBT"
14" Hemlock N 18° W 61 links
"S 6 NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Re-established section corner by measurement to stream north and west.

Position checks with calls of field notes to west.

Found numerous blazes in vicinity.

Distance north to 1/4 corner is longer than Gov't chainage.

Found two spruce stumps in proper position badly rotted. No identifying marks.

SURVEYORS SEAL

SIGNED Billy D. Buckles DATE 8/12/57
REGISTERED LAND SURVEYOR