

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 52 N.R. 35 W


Houghton COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Sections 20-21

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 12-5-63

WITNESSES TO CORNER..... 11" Hard Maple (1/4 S) (NBT) N 76° W 41 links



13" Hard Maple (1/4 S) (NBT) N 54° E 44 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was replaced at Wood Post set by M. Larsen, Hancock.

Corner lies 40.40 chains South of Original Section Corner and checks with stream and hill to North, 1/2 mile to South is short.

Found no original evidence at Corner.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE April 27, 1964
REGISTERED LAND SURVEYOR
Billy D. Buckler