

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD


Houghton COUNTY  
T 52N R 35W

DESCRIPTION OF CORNER Section Corner 13, 14, 23, and 24

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED May 24, 1972

WITNESSES TO CORNER..... Cherry 4 S32°W (mag.) 10.7 ft. "S23, NBT"



Elm 3 N41°E (mag.) 31.0 ft. "S13, NBT"

Red Maple 5 N31°W (mag.) 31.7 ft. "S14, NBT"

AND  
W. Spruce 5 S36°E (mag.) 71.0 ft. "S24, NBT"

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner re-established on line between section corners 79.288 ch. E and 79.609 ch. W. A single proportion was used, rather than a double proportionate, because it appears to more nearly fit the original field note terrain calls to stream crossings to S, W, and N than does a double proportion. Previously acquired measurements in other parts of this township indicate a very erratic original subdivision of the township.

SURVEYOR'S SEAL

DISTRIBUTION:

Forestry Division, Lansing

Area Forester

District Surveyor

SIGNED

*Arthur O. Enger*  
REGISTERED LAND SURVEYOR  
Arthur O. Enger

DATE September 15, 1972