


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Houghton COUNTY
T 52N R 35W

DESCRIPTION OF CORNER Section Corner 11, 12, 13 and 14
CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap
DATE MONUMENT PLACED AND WITNESSED May 24, 1972
WITNESSES TO CORNER..... Cedar 7 N80 $\frac{1}{2}$ °W (mag.) 23.8 ft. "S11, NBT"



Cedar 10 N80°E (mag.) 21.1 ft. "S12, NBT"
Cedar 9 S69°W (mag.) 33.5 ft. "S14, NBT"
AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found 3 old cedar posts or points of posts in place, as set by unknown parties. The found posts bear N28°W 15 lks. from a badly rotted white pine stump corresponding in size with an original BT. Could not identify any marks except axe hacks on the stump, but position is consistent with other known corners in this township. Therefore, accepted posts as marking the original corner location.

SURVEYOR'S SEAL

DISTRIBUTION:

Forestry Division, Lansing

Area Forester

District Surveyor

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE

September 15, 1972