

Noughton Co

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>52</u> N. <u>36.</u> R. <u>35</u> K. <u>W.</u>	<u>J10</u>
2. PROPERTY CONTROLLING IN SECTION <u>26</u>	, T. <u>52</u> N. <u>36.</u> R. <u>35</u> K. <u>W.</u>	<u>12, 15</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 11, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner J10: Found 1 3/4" I.D.xUnknown length Iron Pipe set by Peter A. Larsen on section subdivision prior to 1925.
 - Corner 12: Found 1 3/4" I.D.xUnknown length Iron Pipe set by Peter A. Larsen on section subdivision prior to 1925.
 - Corner 15: Found 1 3/4" I.D.xUnknown length Iron Pipe set by Peter A. Larsen on section subdivision prior to 1925.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner J10: Re-established at pipe.
 - Corner 12: Re-established at pipe.
 - Corner 15: Re-established at pipe.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Corner J10: 1 3/4" I.D.xUnknown Length Iron Pipe
14" Maple N01E 12.1 ft. 1/4S, BT
9" Yellow Birch S16W 21.9 ft. 1/4S, BT
7" Sugar S31E 21.9 ft. 1/4S, BT
 - Corner 12: 1 3/4" I.D.xUnknown length Iron Pipe
8" Hemlock S81W 20.5 ft. 1/16S, BT
9" Sugar S07W 8.0 ft. 1/16S, BT
7" Yellow Birch N70E 18.5 ft. 1/16S, BT
 - CORNER 15: 1 3/4" I.D.xUnknown Length Iron Pipe
5" Yellow Birch N68E 13.6 ft. 1/16S, BT
8" Yellow Birch N46W 33.6 ft. 1/16S, BT
6" Sugar S13W 24.3 ft. 1/16S, BT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE July 14, 1978

CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR
Keith L. Sackett
Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

