

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

(HOUGHTON COUNTY)

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 52 N. R. 35 <input checked="" type="checkbox"/> W.	H5
2. PROPERTY CONTROLLING IN SECTION	15, T. 52 N. R. 35 <input checked="" type="checkbox"/> W.	16, 14
3. MISCELLANEOUS PROPERTY IN SECTION	, T. _____ N. S., R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on (see below), 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner H5: Original monument and accessories not found. Found 1/2" iron pipe set by Melvin C. Larsen from original bearing tree first sighted 1918.

Corner 16: Not set on original survey nor subsequently, apparently.

Corner 14: Not set on original survey nor subsequently, apparently. Found 3" square sugar S47E 20.8 ft. with Longyear Realty Location poster.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner H5: Restored 5-20-80 at M. C. Larsen 1/2" iron pipe.

Corner 16: Established 6-3-80 midway on line between corners east and west.

Corner 14: Established 6-2-80 midway and on line between corners north and south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner H5: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.

7" Sugar N07E 15.0 Ft., 1/4S, NBT

7" Sugar S60W 16.1 Ft., 1/4S, NBT

4" Sugar S58E 11.0 Ft., 1/4S, NBT

Corner 16: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.

7" Sugar N10E 26.2 Ft., 1/16S, BT

22" Hemlock N72E 25.2 Ft., 1/16S, BT

8" Y. Birch S50W 46.4 Ft., 1/16S, BT

Corner 14: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.

8" Sugar N73W 25.7 Ft., 1/16S, BT

6" Sugar S50E 32.8 Ft., 1/16S, BT

6" Maple N30W 17.1 Ft., 1/16S, BT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 7-18-81
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Keith L. Sackett
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

