

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF—	(HOUGHTON COUNTY) LOCATED IN—	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____ S., R. _____ E. W.		_____
2. PROPERTY CONTROLLING IN SECTION <u>15</u> , T. <u>52</u> , N. <u>X</u> , R. <u>35</u> , E. W. <u>X</u>		9, 5, 13
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____, S., R. _____, E. W.		_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on (see below), 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner 9: Not set on original survey nor subsequently, apparently.
  - Corner 5: Not set on original survey nor subsequently, apparently.
  - Corner 13: Not set on original survey nor subsequently, apparently.
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner 9: Established 6-10-80 during section subdivision.
  - Corner 5: Established 6-10-80 during section subdivision.
  - Corner 13: Established 6-12-80 during section subdivision.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Corner 9: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.  
 14" Hemlock S81W 24.0 ft., 1/16S, BT  
 8" Cedar N06W 39.4 ft., 1/16S, BT  
 14" Hemlock S28E 20.7 ft., 1/16S, BT
  - Corner 5: Set 1" I.D. x 36" iron pipe.  
 16" Sugar East 4.8 ft., 1/16S, BT  
 12" Sugar N60W 21.8 ft., 1/16S, BT  
 12" Sugar S70W 12.5 ft., 1/16S, BT
  - Corner 13: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.  
 9" Sugar N03E 14.8 ft., 1/16S, BT  
 5" Y. Birch N78E 6.2 ft., 1/16S, BT      5" Sugar S07E 3.8 ft., 1/16S, BT

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Keith L. Sackett  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR

Keith L. Sackett  
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

