

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

HOUGHTON COUNTY

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 52 N. R. 35 W.	A-12
2. PROPERTY CONTROLLING IN SECTION: 31	T. 52 N. R. 35 W.	3, 7
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner A-12: Original monument and accessories not found.
- Corner 3: Not set on original survey nor subsequently apparently.
- Corner 7: Not set on original survey nor subsequently apparently.

B. Description of corner evidence found and or method applied in restoring or re-establishing corner:

- Corner A-12: Restored 5-20-82 midway and on line between section corners north and south.
- Corner 3: Established 5-20-82 midway and on line between section corner north and 1/4 corner south.
- Corner 7: Established 7-14-82 midway and on line between section corner north and 1/4 corner south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|---|
| <p>Corner A-12: Set 1" I.D. by 32" Iron Pipe w/4" alum. cap.
 8" Maple S30E 11.1 ft. 1/4S, NBT
 8" Sugar N78E 20.6 ft. 1/4S, NBT
 14" Sugar N76W 4.6 ft. 1/4S, NBT</p> <p>Corner 3: Set 1" I.D. by 32" Iron pipe w/4" slum. cap.
 8" Sugar N58E 7.4 ft. 1/16 S, BT
 12" Sugar S13E, 15.3 ft. 1/16S, BT
 3" Sugar S55W 10.6 ft. 1/16S, BT</p> | <p>Corner 7: Set 1" I.D. by 32" Iron Pipe with 4" alum. cap.
 8" Maple S81W 5.8 ft. 1/16S, BT
 12" Hemlock S30E 8.9 ft. 1/16S, BT
 12" Hemlock N48E 13.4 ft. 1/16S, BT</p> |
|--|---|

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 2-16-83
MICHIGAN REGISTERED LAND SURVEYOR

Keith L. Sackett
 Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006