

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Houghton
(County)

	Located In:	Corner Code #/
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S 15 T 52N R 35W 8	8
	S 15 T 52N R 35W 12	12
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Stephan J. Szyszkoski, in a field survey on July 25, 1994, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(8-Sec. 15) West 1/16 corner. Corner established and recorded in 1980 by Keith Sackett, RLS as follows: Set 1" I.D. x 38" iron pipe. 15" Sugar N81W 7.8', 9" Sugar N41E 25.8', 7" Hemlock S01W 16.8'. Found no subsequent record.
 (12-Sec. 15) South 1/16 corner, Section 15. Corner established and recorded in 1980 by Keith Sackett, RLS as follows: Set 1" I.D. x 38" iron pipe. 6" Sugar N80E 17.0', 7" Sugar S70W 15.7', 9" Maple S27E 4.3'. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(8-Sec. 15) Found the 1980 monument disturbed by heavy equipment. Removed the bent pipe and set a 1" I.D. x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet at record bearing and distance from the two remaining 1980 BTs: the 15" Sugar, and the 7" Hemlock. Both are in good condition. The 9" Sugar MBT has been destroyed. Marked two new bearing trees as described below.
 (12-Sec. 15) Found the 1980 monument in good condition at record bearing and distance from two remaining BTs: the 6" Sugar, and the 7" Sugar, both in good condition. The 9" Maple BT is missing. Left the monument in place and marked two additional bearing trees as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(8) Set a 1" iron pipe with MDNR cap. Blazed and scribed the following new bearing trees: 10" Maple S70E 22.4' 1/16S BT" 7" Sugar N33E 40.9' 1/16S BT"	(12) Found 1" I.D. iron pipe. Blazed and scribed the following bearing trees: 4" Sugar N10E 20.4' 1/16S BT" 4" Y. Birch S01E 18.0' 1/16S BT"
--	--



Signed by Stephan J. Szyszkoski Date 8-1-94
 Surveyor's Michigan License No. 33986