

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Houghton

County	Located in:	Corner Code #
1. Public Land Survey	T <u>52N</u> R <u>35W</u>	<u>E12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	1	2	3	4	5	6	7	8	9	10	11	12	13
3	4	5	6	7	8	9	10	11	12	13	14	15	16
4	7	8	9	10	11	12	13	14	15	16	17	18	19
5	10	11	12	13	14	15	16	17	18	19	20	21	22
6	13	14	15	16	17	18	19	20	21	22	23	24	25
7	16	17	18	19	20	21	22	23	24	25	26	27	28
8	19	20	21	22	23	24	25	26	27	28	29	30	31
9	22	23	24	25	26	27	28	29	30	31	32	33	34
10	25	26	27	28	29	30	31	32	33	34	35	36	37
11	28	29	30	31	32	33	34	35	36	37	38	39	40
12	31	32	33	34	35	36	37	38	39	40	41	42	43
13	34	35	36	37	38	39	40	41	42	43	44	45	46

I, Stephen J. Szyzkowski, in a field survey on November 09, 1993, 19\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

**NOTE:** Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

(E12) Quarter corner common to Sections 32-33. Corner restored by Dean C. DeLaMater, RLS, as follows: This corner was found by Forestry Division survey crew, while making a partial resurvey of this Township. Two original B.T.'s still alive, both green, with grown over scars. Corner placed and witnessed August 11, 1953. Placed 1" pipe with 4" brass Mich. Dept. of Conservation cap. NBTs: 14" N. Maple S30E 24 links, 12" Hemlock N85W 7 links.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(E12) The 1953 monument was not recovered. Re-monumented the corner at record bearing and distance from the 1953 NBTs, both in good condition. At the position for the corner, I placed a 1" I.D. x 32" iron pipe capped with a 4" dia. cast aluminum MORA tablet, appropriately stamped. Marked two new witness trees as described below.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(E12) Set 1" pipe with 4" MORA cap.


Blazed and scribed the following new

bearing trees:

12" Sugar N17E 21.8' "1/4S NBT"

8" Sugar S04W 15.2' "1/4S NBT"

Bearings magnetic.



Signed by Stephen J. Szyzkowski Date 2-7-94  
 Surveyor's Michigan License No. 33984