

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Houghton</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S <u>23</u> T <u>52N</u> R <u>36W</u>	<u>11</u>
	S <u>23</u> T <u>52N</u> R <u>36W</u>	<u>10</u>
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

May 26 1998

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

(11-Sec. 23) Southwest 1/16 corner, Section 23. Corner not established in the original survey. On a survey by Robert A. Mick, RLS 16936, made in 1979, and recorded in Vol. 1, Page 637, Houghton Co. Surveyors Map Index, a corner noted as "iron pipe set" is shown but not identified as being the 1/16 corner. The method he used to determine the position of this corner is not stated. No witnesses are shown on the drawing.

(10-Sec. 23) South 1/16 corner between Sections 22-23. Corner not established in the original survey. Corner shown as "iron pipe set" by Robert A. Mick, RLS 16936, on a 1979 survey recorded in Vol 1, Page 637, Houghton Co. Surveyors Map Index. The corner is shown as having been set midway and on a straight line between Section corner 1396.42' Southerly and Quarter corner 1396.42' Northerly.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(11-Sec. 23) Found no evidence of prior monumentation at the proper corner position. Established the corner at the intersection of straight lines connecting opposite 1/16 corners 1432.37' north, 1432.65' south, 1323.00' west, and 1322.79' east. At the position for the corner I placed a 1" IDx32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. From the corner monumented, I found a 1/2" dia. rebar, uncapped, N02E 55.0', and a 1/2" dia. rebar with a plastic cap #16936, N49W 85.6'. Corner placed and witnessed by D.Lampela and B.Wheeler, Baraga District Office.

(10-Sec. 23) The iron pipe noted on the 1979 survey was not recovered. Established the corner midway and on a line of mean true bearing between Section corner 1398.30' Southerly and Quarter corner 1398.30' Northerly. At the position for the corner I placed a 1" IDx60" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. From the position monumented, I found a 1/2" dia. rebar, with no cap, N30E, 2.1 feet. Corner placed and witnessed by D.Lampela and B.Wheeler, Baraga District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(11) Set 1" pipe with 4" MDNR cap.

Blazed and scribed the following:

14" Sugar N31E 13.4' "1/16S BT"

4" Sugar S80E 3.9' do

7" Sugar S03W 17.2' do

12" Y. Birch N30W 33.5' (slope) do

Paced squared sugar post adjacent.

Bearings are magnetic. Distances are to notch in lower blaze.

(10) Set 1" pipe with 4" MDNR cap.

Blazed and scribed the following:

8" Y. Birch N14E 21.7' "1/16S BT"

13" Tamarack S73E 26.8' do

5" Sugar S06W 26.4' do

8" Y. Birch N37W 17.9' do

Placed a squared sugar post adjacent.

Bearings are magnetic. Distances are to notch in lower blaze.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 4-6-99

For the Michigan Department of Natural Resources - Forest Management Division