

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Houghton
 (County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|----------------|-----------------|
| 1. Public Land Survey | T52N R 36W | LINE TREE I9-J9 |
| | T___ R___ | _____ |
| | T___ R___ | _____ |
| | T___ R___ | _____ |
| 2. Property Controlling
in Section | S___ T___ R___ | _____ |
| | S___ T___ R___ | _____ |
| 3. Miscellaneous
Property in Sec. | S___ T___ R___ | _____ |
| | S___ T___ R___ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

May 21 1998

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												


A. Description of original monument and accessories and/or subsequent restoration:
 Line Tree between I9 and J9 on the line between Sections 23-26, 821.2' Easterly of I9. Established in 1846 by Sylvester Higgins : " West Corrected between Sec. 23 and 26 67.62 Cedar 12, 79.99 Sec. Cor." Melvin C. Larsen, in 1961, states in notes for corner I9 " Set I. Pipe for cor... found some old blazes N + S checks with calls to swamp 7 chs. east and a Cedar possible line tree and east over swamp".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

Recovered a hollowed, burned out cedar snag, approximately 4' high, of record size and at the swamp edge as noted in the random line notes. No markings were found on the cedar but they would most likely have been burnt away. By measurement to Larsen's pipe at I9, I confirm that this is the tree he referred to in his notes. There are no other cedars nearby. Distance west to swamp edge checks with the record. Distance west to monument at I9 also checks with the record. Distance east to remonumented K9 is 69.42 ch., the difference not being unusual in this township. I accept this tree as the original line tree marked by Higgins. To preserve this location, I place, in the center of the tree, which is hollow to ground level, a 1" ID x 32" iron pipe capped with a yellow plastic cap stamped "MICH DNR PS 33986". Placed and witnessed by B.Wheeler and D.Lampala, Baraga District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner

Set 1" pipe with yellow plastic cap
 "MICH DNR PS 33986". Blazed and scribed
 the following:
 10" Y. Birch S66E 20.25' "LT BT"
 6" Maple S19W 19.35' do
 8" Cedar N18W 45.80' do
 5" Hemlock N50E 31.65' do
 Distances are to notch in lower blaze.
 Squared a 10" Balsam S80W 1.6' to center
 of tree. Bearings are magnetic.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 4-6-99

For the Michigan Department of Natural Resources - Forest Management Division

T52N-R36W Corner I9
Section corner common to Sections 22-23-26-27.
Field survey date May 21, 1998

Part A Continued from the front:

1961 notes by Melvin C.Larsen, in a retracement of the lines between 22-23 and 26-27: "From the M.C. Cor on the south shore of Lake Roland...run due south magnetic and chained 1.90 I.pipe app. 16' west (old)...33.50 Set temp stake. Set I.Pipe for Cor [22-23-26-27] 42' east. Found some old blazes N&S. checks with calls to swamp 7 ch. east and a cedar possible line tree and east over swamp. NBT maple 8" N48W 12.3', NBT Birch 10" N82E 13.3'"

Part B Continued from the front:

These facts refute the assertion that the 1994 monument represents the position - even approximately - of the original corner. I accept the pipe recorded in 1984 as the best available evidence of the position of the original corner. At the position of the 1" pipe I place a 1" ID iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. The monument was placed and witnessed by D.Lampela and B.Wheeler, Baraga District Office.